

The Henryk Niewodniczanski Institute of Nuclear Physics Polish Academy of Sciences

Overview of IFJ PAN contribution to scientific infrastructures supporting research in applied superconductivity

Dariusz Bocian


for Division of Scientific Equipment and Infrastructure Construction (DAI)

SPAS 2014, Kraków

46



- IFJ PAN and selected projects
 - European XFEL
 - LHC consolidation and upgrade
 - Wendelstein 7X
- Scientific equipment construction
- Summary



Outline

General information



Expertise:

- \rightarrow XFEL (construction)
- → LHC (construction, consolidation, upgrade)
- \rightarrow W7-X (construction)
- \rightarrow AIC-144 (construction, medical applications)
- → **Proteus C235** (medical applications, research)

Scientific activities:

- \rightarrow International:
 - LHC upgrade
- \rightarrow Local (at IFJ PAN) :
 - CCB research program
 - AIC-144 (medical applications)

Staff:

- \rightarrow Scientists: 5
- \rightarrow Engineers: 34
- \rightarrow Technicians: 65

Local infrastructure:

- → cyclotron Proteus C-235
- \rightarrow cyclotron AIC-144 (60 MeV)
- \rightarrow Fast neutron generator (14 MeV)
- \rightarrow Van der Graaf generator (2.5 MeV)



General information: Projects



Running projects:

- -XFEL, DESY, Hamburg, 2009 2015
- -LHC, CERN, Geneva, 2013 2014
- ITER, Cadarache, 2010-2015
- Cherenkov Telescope Array (CTA), 2008 2013





Completed projects

- -LHC, CERN Geneva, 2005 2012
- Wendelstein 7 X, IPP Greifswald, 2007 2012
- ATLAS, CERN Geneva, 2004 2012
- T2K, J-PARC Tokai, Krakow/J-PARC, 2007 2009





- 1) Performance of acceptance tests of *cavities* for a series of 840 units on DESY infrastructure and delivering the corresponding test reports
- 2) Performance of acceptance tests of *cryomodules* for a series of 103 units on DESY infrastructure and delivering the corresponding test reports
- 3) Performance of acceptance tests of *cold magnets* for a series of 103 units on DESY infrastructure and delivering the corresponding tests reports common effort with DESY



XFEL RF cavities tests

DAI



XFEL quadrupole magnets tests



XFEL cryomodules tests





The IFJ PAN work at DESY:

- preparatory phase (2009-2012)
- series tests (2013-2015).

Preparatory phase:

- elaborate scopes of the tests,
- development of measurement software
- design/create data bases for acceptance tests of magnets, cavities and cryomodules;
- prepare test procedures and verify them on existing test-stands
- Perform-tests of prototype and pre-series components (15 cold magnets, 60 cavities and 3 cryomodules)
- prepare required documents (Quality Plan, Risk Assessment, Working Instructions, Inspection/Testing /Non-conformities forms, ...)




Tests of RF cavities




prototype and pre-series cavities – tested

production cavities - testing




Results of RF cavity measurement





Insertion of the cavity into the vertical cryostat



Measurement of the cavity fundamental mode spectra




Tests of accelerator cryomodules



3 prototype cryomodules – tested

3 pre-series cryomodules - tested


100 series cryomodules – testing



Calibration coefficient and check quality factors of the couplers during cryomodule RF test



Prototype module on existing test bench



Leak test of vacuum pipes






15 prototype and pre-series magnets – tested

10 production magnets – tested

90 production magnets – testing



XFEL quadrupole test at cold



XFEL quadrupole magnet test at




XFEL quadrupole inside the cryostat vessel



IFJ PAN effort to XFEL construction





Overview of IFJ PAN contribution to superconducting scientific infrastructures


10



IFJ PAN contribution to LHC construction (2005-2014)



- 1) design & construction of measuring/testing devices
- 2) preparation of necessary software and data bases
- 3) manufacturing of superconducting N-lines
- 4) development of measuring/testing methods
- 5) organization, performance & documentation of electrical measurements /tests
- 6) organization, performance & documentation of interconnection inspection



Mobil test stations in LHC tunnel



User interface



Damaged PIM (Plug-In Module)

DAI



Electrical measurements and tests




2005 – 2010 Thousands of electrical measurements/tests performed in terms of continuity, resistance and HV qualification of superconducting circuits in warm and cold states.

The team, as the first, performed measurements of very low resistance of main bus bar connections at cold (without necessity of opening interconnections between magnets). The measurement results were essential for CERN groups developing a new Quench Protection System.

2011 – 2012 Upgrade of the measuring/testing devices 2013 – 2014 Campaign of measurements/tests has started



Measurements in the LHC tunnel (2005-2010)



Upgraded hardware and software (2011-2012)




Inspection of interconnections



Scope of inspection:

- **Pre-inspection** of a single magnet (visual inspection of all magnet components, checking of beam lines by means of endoscopy and **microwave reflectometry** methods)
- Visual inspection of interconnections (after orbital and ultra-sonic welding)
- Microwave reflectometry measurements of the beam lines in series of connected magnets
- Final visual inspection just before the closure of each interconnection
 - In collaboration with CERN staff, the team developed a method for the localization of damaged PIMs
 - method is two times more precise than that employed before.
 - method could be used without opening the interconnections between magnets.










IFJ PAN effort to LHC

IFJ PAN

Total number of FTEs over 8 years: ~160

Total number of trained IFJ PAN staff: ~50





IFJ PAN contribution to W7-X construction (2007 – 2012)




- IFJ PAN was responsible for the assembly of the bus bar system powering 70 superconducting coils on five modules of the stellarator.
- The bus bars are made of the NbTi superconductors in an aluminium jacket.
- There are 24 bus bars on each module.



QD-wires

2 Capton lavers





Joints assembly



Mechanical and electrical connection of the superconductors




Electrical connection of 81 triplets





Connected triplets squizzed with clamps and covered by stainless steel caps





Electrical insulation of the assembled joints (divided into three steps)

All joints (184) passed successfully tightness and HV tests



Installation of 24 bus bars on the module and final shaping of the bus bar ends

Module Separation Plane set of six joints painted and clamped



Cherenkov Telescope Array (CTA) (2008 – 2013)



- 1. Design and prototyping of Davis Cotton (D-C) telescope structures
- 2. Design and prototyping of composite mirrors.

Ad. 1


IFJ PAN provided a complete design of three Small Size Telescope (SST) structures of various mirror dish diameters (6m, 7.6m, 4m)

Ad. 2

Starting from circular mirror samples of 0.2m and 0.4m diameters IFJ PAN built full size prototypes of hexagonal mirrors for SST (0.78m flat-to-flat, curvature radius 23m) and MST (1.20m flat-to-flat, curvature radius 32m)

Total number of FTE over 6 years > 30

Total number of trained IFJ PAN staff > 10








The design process included:

- structural optimization,
- strain-stress analysis under static and dynamic loads,
- modal analysis,
- cost estimate.

Various types of drive systems of the elevation and azimuth axes were considered.



6 m dish diameter

7.6m dish diameter

4m dish diameter


The D-C SST structure with the mirror dish diameter of 4.0 m will be manufactured in the Polish industry in 2013. Following, it will be tested at IFJ PAN in 2014.






Two prototypes of the open structure mirrors were built for the D-C SST (7.6 m mirror dish diameter). The hexagonal mirrors has size 0.78 m (flat-to-flat), the curvature radius 23 m and weights 16.6 kg. R&D included also performance of ANSYS® simulations.

The prototypes were tested by CTA laboratories. Due to the test results IFJ PAN was recommended to build nine prototype mirrors for D-C Medium Size Telescope (MST). The size of the MST mirrors is 1.2 m (flat-to-flat) and the curvature radius 32 m.







MST **p**rototype mirror (1.20 m, 32 m) PSF (D80) = 17.4mm



Medical equipment construction Proton radiotherapy at IFJ PAN



Components of eye melanoma setup




Device for immediate proton beam cut-off, so called shutter



range discriminators and beam collimators

DAI



Supports for the end of beam line



Holders for digital x-ray recorders




Adjustable supports for x-ray lamps



Scientific equipment construction Finger detector at GSI Darmstadt



Mechanics for one detector – completed in 2012





Scientific equipment construction Stellarator W7 - X



Mechanics for 30 sets of polychromators – completed in 2011



DAI



Scientific equipment construction ATLAS Assembly



Aluminium frame to install Muon Chambers – completed in 2006



The frame at IFJ PAN

The frame used during installation in the ATLAS cavern







- IFJ PAN groups contribute to major world experiments in particle physics, astrophysics and nuclear physics.
- IFJ PAN contributes to XFEL and LHC
- IFJ PAN is involved in fusion projects (W7X, ITER)
- We are ready to do next steps:

 \rightarrow R&D program in applied superconductivity \rightarrow Cryogenic test infrastructure