

INNOVATIONS AND OPERATION OF THE SOLARIS SYNCHROTRON

Adriana Wawrzyniak
On behalf of Accelerator Department

Kraków, 21.10.2024

SOLARIS National Synchrotron Research Centre

adriana.wawrzyniak@uj.edu.pl




OUTLINE


1. Introduction to SOLARIS
2. Main storage ring parameters
3. Operation performance
4. Current development & future plans
5. Summary

INTRODUCTION TO SOLARIS






Solaris is a 3rd generation lights source in user operation mode built in Krakow at JU Campus.



SOLARIS timeline



SOLARIS KEY PERFORMANCE INDICATORS



SOLARIS COLLABORATION



SOLARIS Centre with its modern infrastructure, is a strategic partner in implementing EU-funded projects, supporting innovation and technological development in the region.



**LEAPS
Leadership**
during the EU presidency



CERIC-ERIC
General Assembly

**LIGHT
FOR UKRAINE**
international cooperation



ESFRI
permanent expert



**PALSA
observer**
Pan American Light Sources
for Agriculture


NEW PROJECTS:




RIANA project



international scientific community
project



ESUO
EUROPEAN
SYNCHROTRON
AND FEL USER
ORGANISATION



nephows
Neurons and Proteins
Elevating Worldwide Science

nephows project launched!
Get more information at: www.beamtime.eu

COMPLETED PROJECTS:



SYLINDRA



**LEAPS
INNOVATION**




BEATS





jakub.szlachetko@uj.edu.pl

ACCELERATORS OVERVIEW



- ### 1.5GeV Storage ring
- 12 DBA Cells – 96 m circumference
 - Space for ID's (10 sections) ~ 3.5 m
 - 10 straight sections for IDs
 - 100 MHz RF system
 - 300 MHz Landau Cavities
 - Injection dipole kicker
 - Ramping
 - In operation since May 2015

- ### 600 MeV Linac
- RF Thermionic Gun
 - 6 S-band 2998.5 MHz accelerating structures
 - Accelerating gradient 20 MeV/m
 - 3 RF Units & SLED cavities
 - Dog-leg vertical transfer line
 - In operation since Dec. 2014



See poster presentation on RF system on Tuesday

STORAGE RING PARAMETERS

Storage Ring Magnets (mirror symmetric)

Machined from solid iron, 2 half slabs, ~4.5 m, ~7 Tons each slab


Electron energy	1.5 GeV
Design current	500 mA
Number of circulating bunches	32
Natural bunch length σ_z/w	14.2 mm /60 mm
Landau Cavities (LC)	
Natural emittance (bare lattice)	5.982 nmrad
Coupling	1 %
Energy spread (bare lattice)	0.000745
Tunes ν_x, ν_y	11.22, 3.15
Natural chromaticities ξ_x, ξ_y	-22.96, -17.14
Corrected chromaticities ξ_x, ξ_y	+1, +1
Momentum compaction	3.055×10^{-3}
Energy loss/turn	114.1 keV
Momentum acceptance	4%

Gradient bending magnet with pole-face strips


Combined focusing quadrupole-sextupole magnets

Defocusing sextupole magnets

coil correction magnets (COD, Skew quads, aux. sextupoles)



Optical Functions ($\nu_x = 11.220, \nu_y = 3.150$)



OPERATION STATISTICS

SOLARIS OPERATION


STANDARD OPERATION

- 2 Shifts from Monday to Saturday (8:00-16:00; 14:00-22:00)
 - Monday – machine days, maintenance
 - User operation 5 days/week (Tue-Sat)
 - On call support to 2:00 am from Tuesday-Saturday
 - 2 operators/shift
- Sunday – no injection, beam in the storage ring
- Injection twice/day: 8:00 am and 8 pm
- One operation mode (uniform filling pattern)
- Operation in the decay mode




EXTRA OPERATION:

- Injection upon request on Sundays
- Pilot Sundays - 10 Sundays (April'24-January'25) with 2 injection and on call support




OPERATION OVER LAST YEARS

Operation time distribution




$$\text{Availability} = \frac{\text{Delivered time}}{\text{Scheduled time}}$$




FAILURE STATISTICS

Failures by time





Failures by number



■ B ■ CT ■ DIA ■ MPS ■ ID ■ INF ■ I ■ MML ■ HE ■ OI ■ OT ■ NET ■ MAG ■ PSS ■ RF ■ VAC ■ WAT


■ B ■ CT ■ DIA ■ MPS ■ ID ■ INF ■ I ■ MML ■ HE ■ OI ■ OT ■ NET ■ MAG ■ PSS ■ RF ■ VAC ■ WAT

CURRENT AND LIFETIME




CLOSED ORBIT STABILITY & REPEATABILITY


Closed orbit correction (slow orbit feedback):
 36 beam position monitors (BPMs);
 72 corrector magnets (36 for each plane).
 After beam based calibration the closed orbit is corrected to the sub-micrometer values rms.




Electron beam stability in the submicrometer level




Long-term stability of the photon beam



Repeatability of the injection



Short-term stability of the photon beam



SOLARIS DEVELOPMENT

FAST ORBIT CORRECTION

Fast orbit feedback system development

- ✓ All hardware installations have been finished (24 correctors installed, connected to PS, and Liberas GDX modules).
- ✓ Hardware connections were verified and tested.
- ✓ First proof-of-concept measurements and test runs were performed.
- ✓ The core of the work focuses now on experimentally determining parameter values, control software development and solving problems as they arise.
- ✓ The machine studies time is shared with other new developments, but we expect to have first FOFB-enabled operations next year.







Fig. 2: FOFB hardware

FOFB PERFORMANCE




Reduction of XBPM Standard deviation.




ID's impact compensation – more than 1 order of magnitude correction improvement.

SINGLE BUNCH OPERATION DEVELOPMENT




The Filling pattern measured with fast photodiode at LUMOS beamline.



I=400 mA, t=15h




I=8-12 mA, t=2.5h



BUNCH BY BUNCH FEEDBACK SYSTEM




Demonstrated bunch-by-bunch feedback in all three planes;
The beam is currently transversely stable at 400 mA;
Mode 21 in the vertical plane oscillates at 0.5 μm steady-state amplitude, observation to be confirmed;
Strong longitudinal instabilities are seen above 3.6 mA at 1.51 GeV;
Bunch cleaning was demonstrated at the injection energy, 35 W is sufficient.
Can be also used as a diagnostic tool (tune measurement, beam excitations –machine studies)



Preparations for BBFB: 50 ps rise/fall time edges comparator design

- Typical waveform generator output is too slow for testing power amplifier for Bunch by bunch feedback; for example, 10 ns is not acceptable
- In Solaris we designed, assembled and tested ultra fast comparator to reach rise and fall edge times of around 50 ps
- Together with typical, slow generator, we got rise/fall time ca. 135 ps, but measured value is a limitation of our oscilloscope analogue bandwidth




INSTALLATION AND START-UP OF BBQ MEASUREMENT SYSTEM

BBQ (Base-Band Q) system will allow us to measure TUNE without exciting the beam based on a direct diode detection method initially designed for the LHC. This allows a reliable tune measurement with micrometre or even sub-micrometre beam oscillations. It is dedicated systems optimised for beam oscillation detection. In these systems the static beam position is rejected at a very early stage with only the oscillation signal retained for further processing. Front-end and control panel have been installed inside the ring. Measured signal 10-16 dB above noise, during operation. The maximum voltage on the detectors is $\sim 80V$ at a current of 450mA.


- Further development:
- dedicated acquisition system
 - TUNE feedback system



Device in the Storage Ring



Spectrum of the beam




BBQ Frontend

NEW BEAMLINES DEVELOPMENT


Modification of the storage ring - Beamline CIRI

CIRI Chemical InfraRed Imaging, is a specialized research installation using infrared light. CIRI will ultimately be equipped with three end stations for imaging in micro- and nanometric spatial resolution.



First stage – design and install new dipole vacuum chamber VK1m

Second stage – design and install new beamline inside storage ring (in progress)



Design by SOLARIS!

Third stage – low vacuum system and endstations at experimental hall


NEW BEAMLINES DEVELOPMENT -CIRI

Modification of the storage ring - Beamline CIRI (first stage) – summer 2023




NEW BEAMLINES DEVELOPMENT -CIRI



Preassembly at the experimental hall
Spring 2024



Installation in the storage ring
Summer 2024





First Light @ end of CIRI
26th August 2024



NEW BEAMLINES DEVELOPMENT -SOLCRYS

- Order for the source 3PW placed in June 2023
- Expected delivery November 2024
- The conceptual design of the straight section done
- Place holder for new injection kicker foreseen
- Placing the order for vacuum components under preapration
- FE tender under preparation






Local correction of flanking dipoles gradient of 3% & 2.5 % increase

Global correction of dipoles gradient 0.25% decrease


LINAC UPGRADE – NEW CONCEPT

See poster presentation on Linac upgrade on Tuesday

Layout of the S-band linac with 14 High Gradient (HG) structures (35MV/m) combined in 7 RF Units



For short prototype an accelerating gradient of 40 MV/m with input RF power of 125 MW was demontsrated*



*N. Shafqat, C. Serpico, T.G. Lucas „Design and high-power test of a short prototype of high gradient S-band accelerating structure for the FERMI free electron laser linac upgrade”, J.NIMA, [Volume 979](https://doi.org/10.1016/j.nima.2020.16447), 1 November 2020, 164473 <https://doi.org/10.1016/j.nima.2020.16447>

BUNCH LENGTH MEASUREMENT BY COHERENT DIFFRACTION RADIATION (CDR)




Figure 1: CDR spectral-angular distribution for the SOLARIS injector bunch repetition pattern and beam energy of 550 MeV.




Figure 2: Bunch length to power ratio, corrected for diode aperture.




Figure 3: Experimental setup.




Figure 4: Signals measured by diodes with different bands.

SUMMARY

1. Solaris is a **3rd generation lights source** in **user operation** mode and in **constant development** of the infrastructure.
2. **The beam availability** in 2024 is **97.5%** with MTBF of **190.5 h** and MTTR of **4.3 h**
3. **Fast Orbit Feedback (FOFB) system is now deployed** and **operational** since April with extremely good ID movement compensation.
4. **Tune measurement and tune feedback project is under development.**
5. **Bunch by Bunch Feedback system** purchased and to be installed by end of this year.
6. **4 additional Beamlines: CIRI** – installed-first light at the end in August, **SOLCRYS , SMAUG and NAP-XPS**– design and purchase, **are underway**
7. **Design work on linac upgrade and top up injection scheme** in ongoing.
8. **Other modes** (single bunch, camshaft, dedicated filling patterns) of operation are **under development.**



Thank you for your attention!

THE LORD OF THE RINGS
THE FELLOWSHIP
OF THE RING

